

15-185-20747-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 28 Twp. 25S Rge. 15W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

C NE/4
Lease Owner Alpine Drilling Company, Inc.
Lease Name Payton #2 Well No. 2

Office Address 800 Bitting Building, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed July 7, 1977 19
Application for plugging filed July 7, 1977 19
Application for plugging approved July 7, 1977 19
Plugging commenced 6:30 AM, July 7, 1977 19
Plugging completed 8:30 AM, July 8, 1977 19
Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4342'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	260'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Spotted 40 sacks cement at 270' thru open end drillpipe. Mud to 40', 1/2 sack hulls.
Wood plug and 12 sacks to surface;
3 sacks in rat hole.

RECEIVED
CONSERVATION DIVISION
JUL 12 1977
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY


(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of July, 1977

CHARLES HALL—NOTARY PUBLIC
My Commission Expires Jan. 6, 1978

Charles M. Hall
Charles M. Hall, Notary Public.

My commission expires



Locate well correctly on above Section List

15-185-20747-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- PAYTON #2

Located: C NE/4, Section 28-25S-15W, Stafford County, Kansas

OWNER: Alpine Drilling Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 27, 1977

COMPLETED: July 7, 1977

TOTAL DEPTH: 4342'

LOG	
0 - 220	Sand and Clay
220 - 265	Shale
265 - 930	Red Beds and Sand
930 - 983	Red Beds
983 - 1001	Anhydrite
1001 - 1645	Shale and Shells
1645 - 1675	Shale
1675 - 3832	Lime and Shale
3832 - 3875	Lime
3875 - 3955	Lime and Shale
3955 - 4035	Lime
4035 - 4225	Lime and Shale
4225 - 4304	Lime - Chert
4304 - 4342	Chert, Lime and Shale

CASING RECORD

Ran 6 joints 8 5/8" OD surface casing, 251' cemented at 260' K.B. with 225 sacks. Regular with 2% gel and 3% cc. Plug down at 8:45 PM, 6-27-77.

RECEIVED
STATE CONSERVATION COMMISSION
JUL 12 1977
7-12-77
CONSERVATION DIVISION
Wichita, Kansas

Plugged.