


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15-185-11861-0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County, Sec. 1 Twp. 25 S Rge. 15 W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW SW NE  
Lease Owner Sierra Petroleum Co., Inc.  
Lease Name Waters-Grossman Well No. 2  
Office Address 208 Petroleum Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry  
Date well completed 12/17/59 19  
Application for plugging filed 12/17/59 19  
Application for plugging approved 12/17/59 19  
Plugging commenced 12/17/59 19  
Plugging completed 12/17/59 19  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Stafford, Kansas Rt. #1  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4315 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	272	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGING REPORT

Filled hole with heavy mud from 4315 up to 250'. Set bridge using 1/3 sks hulls, wood plug and 20 sks cement through drill pipe. Filled hole with heavy mud up to 35'. Set bridge using 1/2 sks hulls, wood plug and 10 sks cement to cellar 0. Job completed 8:45 pm 12/17/59

12-21-59  
STATE CORPORATION COMMISSION  
DEC 21 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sierra Petroleum Co., Inc.  
Address 208 Petroleum Bldg., Wichita Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
C. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker

(Address)

SUBSCRIBED AND SWORN TO before me this 18 day of December, 19 59

1-30-61

Margie Cooper

Notary Public.

My commission expires \_\_\_\_\_



15-185-11861-0000

Sierra Petroleum Co., Inc. - Operator

WATERS-GROSSMAN #2

NW SW NE Sec 1-25S-15W  
Stafford County, Kansas

Total Depth: 4315

Elev: 2025 KB

Comm: 12/4/59  
Comp: 12/17/59

Casing:

Cement

8 5/8 @ 272

with 200 sks

FORMATION	DEPTH
Sadd	165
Shale	290
Red Bed	977
Anhydrite	998
Shale & shells	1830
Lime & shale	3540
Lime	3638
Lime & shale	3807
Lime	4238
Mississippi	4290
Lime & shale	4315

Tops:		DEPTH
Anhydrite		977
Heebner		3625
Toronto		3670
Douglas		3688
Brown Lime		3795
Lans. K.C.		3818
Base K.C.		4088
Conglomerate		4172
Mississippi		4223

12-21-59  
 STATE OF KANSAS  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) ss:  
 COUNTY OF RUSSELL )

I hereby certify that the above information is true  
 and correct to the best of my knowledge.

C. P. Hancock

Subscribed and sworn to before me this 18th day of December,  
 1959.

Margie Cooper  
 Notary Public

My commission expires: 1-30-61.