

15-185-11090-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 1 Twp. 25 Rge. 15 (E) W (W)

Location as "NE/CNW&SW&" or footage from lines NW NW NE
Lease Owner Specter Pipe & Supply, Inc.
Lease Name Waters Grossman Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 5-21-59 19__
Application for plugging filed 1-3-66 19__
Application for plugging approved 1-1-66 19__
Plugging commenced 4-11-66 19__
Plugging completed 4-16-66 19__
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation ar buckle Depth to top 4413' Bottom 4414' Total Depth of Well 4422 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	270'	None
				5-1/2"	4413'	2215'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4270', sanded hole to 4220', then to 4170' and dumped 5 sacks of cement @ 4170' with dump bailer. Pulled 5 1/2" casing, set rock bridge from 250' to 240' and dumped 13 sacks of cement @ 240'. Bailed hole to 235' and dumped 22 sacks of cement. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 - 1966
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of April, 19 66

My commission expires May 20, 1968 Milton J. Volin Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-185-11090-0000

Company. SIERRA PETROLEUM CO. & HOUSTON
 Farm. Waters-Grossman No. 1

SEC. 1 T. 25 R. 15W
 NW NW NE

Total Depth. 4422'
 Comm. 5-7-59 Comp. 5-21-59
 Shot or Treated.
 Contractor. Sierra Petro.
 Issued. 9-19-59

County Stafford
 KANSAS



Elevation. 2016' KB

Production. 11 BOPD

CASING:

8 5/8" 270' cem w/200 sx.
 5 1/2" 4413' cem w/100 sx.

Figures indicate Bottom of Formations.

clay & sand	125
sand, shale & shell	270
shale & shell	1400
salt, shale & shell	1695
shale & lime	3845
lime	4129
lime & shale	4160
Mississippi	4230
Kinderhook	4323
Viola	4419
Arbuckle	4422
Total Depth	

TOPS:	
Anhydrite	955
Heebner	3613
Toronto	3631
Douglas	3653
Brown Lime	3761
Lansing-Kansas City	3780
Base Kansas City	4080
Conglomerate	4122
Mississippi	4173
Viola	4289
Simpson (scout)	4342
Arbuckle	4413

RECEIVED
 STATE CORPORATION COMMISSION

APR 4 1966

CONSERVATION DIVISION
 Wichita, Kansas