


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 1 Twp. 25 Rge. (E) 15 (W)
Location as "NE/CNW/SW" or footage from lines NW SW SW
Lease Owner McAdams Pipe & Supply Company
Lease Name Reese Well No. 1
Office Address Drawer 960, Bristow, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed January 10 1968
Application for plugging approved 19
Plugging commenced January 27 1968
Plugging completed February 19 1968
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 4428 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	274'	8 5/8"	274'	none
		0	4417'	5 1/2"	4417'	3213.15

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand back to 4375' and dumped 5 sacks cement.

Pushed plug to 260', set 10' rock bridge and dumped 5 sacks cement.
Set 10' rock bridge at 250' and dumped 25 sacks cement. Filled hole with mud to 40', set 10' rock bridge and capped hole with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of February, 1968

My commission expires July 7, 1968 Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


15-185-01573-0000
COPY

Company. HELMERICH & PAYNE, INC.
Farm- Reese No. 1

SEC. 1 T. 25 R15W
NW SW SW

Total Depth. 4428'
Comm. 12-3-60 Comp. 12-16-60
Shot or Treated.
Contractor. Sierra Petro. Co.
Issued. 5-27-61

County Stafford
KANSAS



CASING:
8 5/8" 274' cem w/225 sx.
5 1/2" 4417' cem w/200 sx.

Elevation. 2019' KB

Production. 180 BOFD

Figures indicate Bottom of Formations.

sand & gravel	160
shale & shells	440
sand	485
red bed & shale	675
red bed	958
Anhydrite	984
shale & shells	1305
salt & shale	1540
shale & shells	1785
shale & lime	3725
lime	4085
lime & shale	4190
Mississippi	4263
cherty lime	4301
Viola	4370
Simpson	4410
Arbuckle	4417
Arbuckle	4428
Total Depth	

TOPS:	
Anhydrite	958
Topeka	3201
Heebner	3608
Toronto	3628
Douglas	3648
Brown Lime	3751
Lansing-Kansas City	3773
Mississippi	4186
Kinderhook	4246
Viola	4264
Simpson	4379
Arbuckle	4413

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1968
CONSERVATION DIVISION
Wichita, Kansas