

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. 1 Twp. 25 Rge. (E) 15 (W)
Location as "NE/CNW/SW" or footage from lines C SW NE NW
Lease Owner Rosen Oil Company
Lease Name Reese Well No. 2
Office Address 260 Sutton Place, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed December 1 1969
Application for plugging approved 19
Plugging commenced December 9 1969
Plugging completed December 22 1969
Reason for abandonment of well or producing formation depleted
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation Depth to top Bottom Total Depth of Well 4398 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	328'	8 5/8"	328'	none
		0	4392'	5 1/2"	4392'	3055.12

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 4100' and dumped 5 sacks of cement.

Squeezed well with 15 sacks gel mud and 75 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 5 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31 day of December, 1969

My commission expires Feb. 10, 1971

George A Meyer
Notary Public.

15-185-11092-0000
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- THE GULF OIL COMPANY
Farm- L. Reese No. 2

SEC. 1 T. 25 R. 15W
SW NE NW

Total Depth. 4395'
Comm. 6-25-60 Comp. 7-10-60
Shot or Treated.
Contractor. Sierra Petroleum Co., Inc.
Issued. 9-3-60

County Stafford
KANSAS



CASINO:

8 5/8" @ 328' w/120 sks. oem.
5 1/2" @ 4393.05' w/250 sks. oem.

Elevation. 2021' RB

Production. 73 BOPD

Figures Indicate Bottom of Formations.

sand	100
shale	405
red bed	956
Anhydrite	981
shale & shells	1395
salt	1423
shale & shells	1860
lime & shale	3505
lime	3568
lime & shale	3725
lime	4213
Kinderhook	4250
shale & chert	4306
lime	4344
Simpson	4389
Arbuckle	4395
Total Depth	

RECEIVED
STATE CORPORATION COMMISSION
DEC 1 1 1969
CONSERVATION DIVISION
Wichita, Kansas

SCOUT TOPS:

Heebner	3593
Lansing	3754
Base Kansas City	4020
Mississippi	4159
Kinderhook	4206
Viola	4260
Simpson	4360
Arbuckle	4389