

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-185-11573-0000
WELL PLUGGING RECORD

NORTH

			11

Locate well correctly on above
Section Plat

Stafford County, Sec. 11 Twp. 25S Rge. 15 (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner White Eagle Oil Co.
Lease Name Wilson "A" Well No. 1
Office Address 619 1st National Bldg. - Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-21 19 53
Application for plugging filed 8-24 19 53
Application for plugging approved 8-25 19 53
Plugging commenced 8-28 19 53
Plugging completed 8-31 19 53
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives Pratt, Kansas
Producing formation Arbuckle Depth to top 4456 Bottom 4465 Total Depth of Well 4465 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing	Salt Water	3780	4199	8-5/8"	285'	None
Mississippian	" "	4199	4229	5-1/2"	4380	2996
Viola	" "	4288	4393			
Simpson	" "	4393	4457			
Arbuckle	" "	4457	4465			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 25 sacks Gel Mud & 25 sacks Wt. Mud at 2600'
Squeezed surface pipe with 5 sacks Gel - Plugged with 85 sacks cement by Halliburton.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pulling Inc.
Address 629 W. Broadway - Stafford, Kansas

STATE OF Kansas, COUNTY OF Stafford, ss.
M. J. Heald Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. J. Heald Jr. Chief Engineer
619 1st National Bldg. - Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September, 19 53

My commission expires 8-19-57

Daquon T. Talbot
Notary Public.

PLUGGING
FILE SEC 11 T 25 R 15 W
BOOK PAGE 124 LINE 27

SEP 18 1953 9-18-53
CONSERVATION DIVISION
Wichita, Kansas

15-185-11573-0000

D R I L L E R ' S L O G

COMPANY: WHITE EAGLE OIL COMPANY LOCATION: SW SW NE 11-25-15
 CONTRACTOR: HILTON DRILLING COMPANY, INC. Stafford County
 Kansas
 FARM NAME: WILSON "A" NO. 1 ELEVATION: 1852 D.F.
 COMMENCED: 7-1-53
 COMPLETED: 7-21-53

Casing Used: 8 5/8 set at 285' w/250 sacks
 5 1/2 set at 4380' w/100 sacks

Send, gravel and clay	154
Blue shale	295
Red Bed	980
Anhydrite	1000
Shale and shells	1610
Lime and shale	1835
Lime	2700
Lime and shale	3145
Lime	3215
Lime and shale	3408
Lime	3681
Lime and shale	3748
Lime, shale, and sand	3791
Lime	4071
Lime and shale	4125
Lime	4171
Lime conglomerate	4228
Chert	4230
Chert, shale, and lime	4256
Shale and chert	4281
Chert and lime	4309
Shale, chert, and lime	4343
Chert and lime	4370
Chert, lime, and shale	4408
Shale, sand, and lime	4453
shale	4460
Lime	4465
Total Depth	4465

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

FILED
 AUG 1 1953
 8-25-53
 DIVISION

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.

Henry Peacock
 Henry Peacock, Secretary

Subscribed and sworn to before me this 23rd day of July, 1953.

Margaret L. Luttrell
 Notary Public

My commission expires April 4, 1956.

PLUGGING
 FILE SEC 11 T 25 R 15w
 BOOK PAGE 24 LINE 27