

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
300 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/82

15-185-11096-0000

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and FILE ONE Copy)

API # 10-13-59 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Redstone Oil & Gas Company KCC LICENSE # 30040 ^{7/95}
(owner/company name) (operator's)
ADDRESS 8235 Douglas Ave. Suite 1050 CITY Dallas

STATE Texas ZIP CODE 75225 CONTACT PHONE # (214) 378-0202

LEASE Grunder WELL# 2 SEC. 11 T. 25S R. 15 (~~East~~/West)

- NW - NE - NE SPOT LOCATION/OQQQ COUNTY Stafford

 FEET (In exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

 FEET (In exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8 SET AT 281 CEMENTED WITH SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 4431 CEMENTED WITH SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: KC3893-3908 3935-40 Miss. 4196.5-

ELEVATION 2018 T.D. 4434 PSTD 4280 ANHYDRITE DEPTH 4210.5 CIBP 4280
(~~ft.~~/K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING: According to the rules and regulations of the
State of Kansas. See Attached Sheet

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED?

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 ~~and~~ ^{and} THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Wayne Roberts PHONE# 405 254-9198

ADDRESS P. O. Box 278 City/State Woodward, Oklahoma

PLUGGING CONTRACTOR Chase Well Service KCC LICENSE # 6123 ^{6/94}
(company name) (contractor's)

ADDRESS P. O. Box 355 Great Bend, Kansas PHONE # (316) 793-9556

PROPOSED DATE AND HOUR OF PLUGGING (if known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-113) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6-21-94 AUTHORIZED OPERATOR/AGENT: Wayne Roberts
(signature)

GL:
KB: 2018

LEASE NAME: Grunder #2
LOCATION : NW-NE-NE
 : Sec 11 T 25-S 15W
COUNTY : Stafford
STATE : Kansas

← 8 5/8 @ 281'

137 jts. 2 3/8 4.7 # Tbg.
@ 4257

← Kansas City
3898' - 3908'
3935' - 3940' 10-7-71
60 - holes

← Lower Mississippi
4196. 1/2 - 4210. 1/2 10-18-59
56 - holes

← Baker P-1 CIBP @ 4280
10-6-71

← 5 1/2" 14# csg. @ 4431'

TD: 4434

Arbuckle formation 4429' - 32

RECEIVED
STATE CONSERVATION COMMISSION
JUN 27 1994
CONSERVATION DIVISION
Wichita, Kansas

REDSTONE



OIL & GAS COMPANY

June 21, 1994

State Of Kansas
State Corporation Commission
Conservation Division
Wichita, Kansas 67202

REF: Proposal for Plugging Well
Grunder #2

Dear Sir:

Redstone Oil & Gas Company purposes to pull Rods and Tubing. Then pump down 5 1/2 casing w/400 lbs. cotton seed hulls. Mixed in 25 sacks 60-40 POZ w/6% gel cement. Followed w/gel spacer to 1000' and cement to surface. Pumping 150 sacks cement down 8 5/8 casing. Then cut off all casing 5' below ground level & weld on cap.

Sincerely,

REDSTONE OIL & GAS COMPANY

Wayne Roberts
Operation Superintendent
of Drilling, Completion & Workover

/ln

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1994
CONSERVATION DIVISION
Wichita, Kansas

PO. BOX 278
WOODWARD, OKLAHOMA 73802

(405) 254-9198
FAX (405) 254-3342



Kansas Corporation Commission

Joan Finney, Governor Susan M. Seitsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

June 27, 1994

Redstone Oil & Gas Company
8235 Douglas Ave Suite 1050
Dallas TX 75225

Grunder #2
API 15-N/A
NW NE NE
Sec. 11-25S-15W
Stafford County

Dear Wayne Roberts,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760