

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CG-1  
Rev. 03/82

15-185-10335-0000

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 6-15-59 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate (spud) or completion date.

WELL OPERATOR Redstone Oil & Gas Company KCC LICENSE # 30040<sup>2/95</sup>  
(owner/company name) (operator's)  
ADDRESS 8235 Douglas Ave. Suite 1050 CITY Dallas

STATE Texas ZIP CODE 75225 CONTACT PHONE # (214) 368-0202

LEASE Grunder WELL# 1 SEC. 11 T. 25S R. 15 (~~East~~/West)

C -S 1/2 SE - NE SPOT LOCATION/QCQQ COUNTY Stafford

\_\_\_\_\_ FEET (In exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

\_\_\_\_\_ FEET (In exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL \_\_\_\_\_ DGA \_\_\_\_\_ SWD/ENHR WELL \_\_\_\_\_ DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 292 CEMENTED WITH \_\_\_\_\_ SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 4235 1/2 CEMENTED WITH 125 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Mississippi - 4226-32

ELEVATION 2016 T.D. 4252 PSTD 4236 ANHYDRITE DEPTH N/A  
(G.S./K.S.) (Stone Corral Formation)

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR  CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING According to the rules and regulations STATE CORPORATION COMMISSION

State of Kansas. See Attached Sheet

JUN 27 1994

(If additional space is needed attach separate page) CONSERVATION DIVISION  
Wichita, Kansas

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? N/A

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Wayne Roberts PHONE# (405) 254-9198

ADDRESS P. O. Box 278 City/State Woodward, Oklahoma

PLUGGING CONTRACTOR Chase Well Service KCC LICENSE # 6123<sup>6/94</sup>  
(company name) (contractor's)

ADDRESS P. O. Box 355 Great Bend, Kansas PHONE # (316) 793-9556

PROPOSED DATE AND HOUR OF PLUGGING (If known?) \_\_\_\_\_

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6-21-94 AUTHORIZED OPERATOR/AGENT: Wayne Roberts  
(signature)

GL:  
KB: 2016

LEASE NAME: Grunder #1  
LOCATION : C 5 1/2 SE NE  
          Sec. 11-T25S-15W  
COUNTY : Stafford  
STATE : Kansas

← 8 5/8 @ 292'

← Hole in 5 1/2" csg. @ 373' - 465'  
cmt w/ 100 sks. 8/29/83

2 7/8" - 6.5# Tbg @ 4219'  
136 jts.

← Perforations, Mississippi  
4226' - 4232'  
24 holes

← 5 1/2 csg. 14# @ 4236"  
cmt w/125 sks.

TD: 4252' 5" hole from 4236' to 4252' 7-8-59

RECEIVED  
STATE CORPORATION COMMISSION  
7-9-59

**JUN 27 1994**

CONSERVATION DIVISION  
Wichita, Kansas

REDSTONE



OIL & GAS COMPANY

June 21, 1994

State Of Kansas  
State Corporation Commission  
Conservation Division  
Wichita, Kansas 67202

REF: Proposal for Plugging Well  
Grunder #1

Dear Sir:

Redstone Oil & Gas Company purposes to pull Rods and Tubing. Then pump down 5 1/2 casing w/400 lbs. cotton seed hulls. Mixed in 25 sacks 60-40 POZ w/6% gel cement. Followed w/gel spacer to 1000' and cement to surface. (Testing 8 5/8 Annlus to 500 PSI.) (If 8 5/8 doesn't test.) Pumping 150 sacks cement down 8 5/8 casing. Then cut off all casing 5' below ground level & weld on cap.

Sincerely,

REDSTONE OIL & GAS COMPANY

Wayne Roberts  
Operation Superintendent  
of Drilling, Completion & Workover

/ln

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 27 1994  
CONSERVATION DIVISION  
Wichita, Kansas

PO. BOX 278  
WOODWARD, OKLAHOMA 73802

(405) 254-9198  
FAX (405) 254-3342



## Kansas Corporation Commission

Joan Finney, Governor    Susan M. Seltsam, Chair    F.S. Jack Alexander, Commissioner    Rachel C. Lipman, Commissioner  
Judith McConnell, Executive Director    Brian Moline, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

June 27, 1994

Redstone Oil & Gas Company  
8235 Douglas Ave Suite 1050  
Dallas TX 75225

Grunder #1  
API 15-N/A  
C S/2 SE NE  
Sec. 11-25S-15W  
Stafford County

Dear Wayne Roberts,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City KS 67801  
(316) 225-6760