

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
244 North Water
Wichita, KS 67202

API Number 15 185-20153-0000 (of this well)

Operator's Full Name Montgomery Drilling Program.

Complete Address 235 Montgomery St., Suite 1114, San Francisco., Cal. 94104

Lease Name Grunder Well No. 1

Location 150' NW NW SE Sec. 26 Twp. 25s Rge. 15 (E) (W) X

County Stafford Total Depth 4280

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176-Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11:15 Am. Day 9 Month 9 Year 1980

The above well was plugged as follows:

295' 8 5/8" casing. 4 1/2" casing set at 4272' w/75 sax cement. Sand back
to 4200'-Top sand w/4 sax mixed cement w/dump bailer. Pull 3794'
casing-Allied mixed & pumped in 8 5/8" casing 8 sax hulls-25 sax gel-
125 sax 50/50 posmix cement w/4% gel & 3% cc to top of casing. Shut
in w/0 pressure.

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1980

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 9-12-80

INV. NO. 30892