

15-185-11090-0000

Form CP-3
Rev. 6-26-62

14
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
KANSAS STATE CORPORATION COMMISSION

APR 18 1966

4-18-66

Operator's Full Name Spector Pipe & Supply, Inc.

Complete Address: Box 169, Russell, Kansas

Lease Name Waters-Grossman Well No. # 1

Location NW NW NE Sec. 1 Twp. 25 Rge. 15 (E) (W)W

County Stafford Total Depth 4422'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 3:45PM Day 16th Month April Year 1966

The Above well was plugged as follows:

270' of 8 5/8" surface pipe, cement circulated. 4413' of 5 1/2" long string,
cemented with 100 sacks. Plug back T.D. 4270'. Bottom of the hole was
sanded to 4170', and cemented with 5 sacks. 2218' of 5 1/2" long string, was
recovered from the hole. Bridge plug was pushed in fluid to 250', rock
bridge from 250' to 240'. 10 sacks of cement and calicum chloridge was
mixed in a barrel, and put on plug at 240', through the dump bailer, and
let set over-night. Next day hole was bailed dry, and 25 sacks of cement
was added to the plug. Hole was filled with mud to 40', rock bridge from
40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/18/66
INV. NO. 3062-w