

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued January 16, 1968.

RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name McAdams Pipe & Supply Company

Complete Address: Drawer 960, Bristow, Oklahoma 74010

Lease Name Reese Well No. # 1

Location NW SW SW Sec. 1 Twp. 25 Rge. 15 (E) (W)W

County Stafford Total Depth 4428'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractors: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 12:45PM Day 19th Month February Year 1968

The Above well was plugged as follows:

274' of 8 5/8" surface pipe, cemented with 225 sacks. 4417' of 5 1/2" long string,
cemented with 200 sacks. This is an open hole. Bottom of the hole was sanded to
4375', cemented with 5 sacks, through the dump bailer, with cement from 4375' to
4335'. 3213' of 5 1/2" long string was recovered from the hole. Bridge plug was
pushed in fluid to 250', bridge plug and rock bridge from 250' to 240'. 5 sacks
of cement was mixed in a barrel, and put on plug at 240', through the dump bailer
and let set for 1 week. Hole was bailed dry, and 20 sacks of cement was added to
the plug, with cement from 240' to 165'. Hole was filled with mud to 40', rock
bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving
Well Plugging Supervisor

INVOICED

DATE 2/21/68

INV. NO. 7298-W