

15-185-01574-0000

Form CP-3  
Rev. 6-26-62

*M*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued January 9, 1968.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 29 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name McAdams Pipe & Supply Company

Complete Address: Drawer 960, Bristow, Oklahoma 74010

Lease Name Reese Well No. # 2

Location SW NW SW Sec. 1 Twp. 25 Rge. 15 (E) (W)W

County Stafford Total Depth 4439'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 10:45AM Day 27th Month January Year 1968

The Above well was plugged as follows:

272' of 8 5/8" surface pipe, cemented with 210 sacks. 4436' of 5 1/2" long string,  
cemented with 200 sacks. This is an open hole. Bottom of the hole was sanded to  
4400', and cemented with 5 sacks, through the dump bailer, with cement from  
4400' to 4350'. 3157' of 5 1/2" long string was recovered from the hole. Bridge  
plug was pushed in fluid to 260', bridge plug and rock bridge from 260' to 250'.  
4 sacks of cement was mixed in a barrel, and put on plug at 250', through the  
bailer, and let set over-night. Next day hole was bailed dry, and 21 sacks of  
cement was added to the plug. Hole was filled with mud to 40', rock bridge from  
40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 1/29/68  
INV. NO. 7164-4