

 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued January 9, 1968.

Operator's Full Name McAdams Pipe & Supply, Inc.

Complete Address: Drawer 960, Bristow, Oklahoma 74010

Lease Name Reese Well No. # 3

Location NE SW SW Sec. 1 Twp. 25 Rge. 15 (E) (W) W

County Stafford Total Depth 4434'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 9:30AM Day 9th Month February Year 1968

The Above well was plugged as follows:

276' of 8 5/8" surface pipe, cemented with 225 sacks. 4290' of 5 1/2" long string,
cemented with 125 sacks. This is an open hole. Plug was pushed to 4200', sand
from 4200' to 4150', and cemented with 5 sacks, through the dump bailer, with
cement from 4150' to 4110'. 3330' of 5 1/2" long string was recovered from the hole.
Bridge plug was pushed in fluid to 260', bridge plug and rock bridge from 260' to
250'. 5 sacks of cement was mixed in a barrel, and put on plug at 250', through
the dump bailer, and let set over-night. Next day hole was bailed dry, and 20
sacks of cement was added to the plug, with cement from 250' to 175'. Hole was
filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks,
with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving
Well Plugging Supervisor

INVOICED
DATE 2/13/68
INV. NO. 7253-W