

15-185-00473-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Robert F. White
Complete Address 714 Union Center Wichita, Ks. 67202
Lease Name Wilson Well No. 1
Location SE/SE/SW Sec. 11 Twp. 25 Rge. 15 (E) (W) W
County Stafford Total Depth 4280
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Russ Casing Pulling Inc.
Address Box 1082 Great Bend, Ks License No. 623
Operation Completed: Hour 3:00PM Day 18 Month 3 Year 1970

The above well was plugged as follows:

315 ft of 8 5/8 surface pipe circulated with cement. 4277 ft of
5 1/2 cemented with 50 sacks. Top perf 4237 ft. Sand back to 4150 ft,
5 sacks cement with bailer. 2900 ft of 5 1/2 pulled. Mud to 260 ft,
10 ft, rock bridge, 25 sacks cement. Mud to 40 ft, 10 ft rock
bridge. 10 sacks cement to top of surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/20/70
INV. NO. 1616-W

Signed: [Signature]
Well Plugging Supervisor