

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-24866-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 12-17S-26W  
2278 feet from S Section Line, 347 feet from E Section Line  
Lease Name: QUENZER "B" Well #: 3  
County: NESS Total Vertical Depth: 4600 feet

Operator License No.: 8653  
Op Name: PETROLEUM TECHNOLOGIES, INC.  
Address: 801 W 47TH ST STE 412  
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4470		WITH 2 SX CMT
PC	5.5	1916		CEMENTED WITH 625 SX CMT
PROD	5.5	4596	0	WITH 775 SX CMT
SURF	8.625	235		WITH 235 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/04/2015 8:30 AM  
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.  
Proposal Rcvd. from: HUNTER HEMBREE Company: STEVE'S WELL SERVICE, INC. Phone: (620) 792-4138

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/04/2015 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4470' WITH 2 SX CMT. RUN TBG TO 1910' & PUMPED 200 SX CMT WITH 400# HULLS. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 30 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4521	4527		

KCC WICHITA  
NOV 23 2015  
RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier  
SA (TECHNICIAN)

CKM 12/2/15

RECEIVED  
NOV 17 2015  
KCC DODGE CITY