

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-20029-00-00
Spot: SWSE Sec/Twnshp/Rge: 28-14S-27W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: CHENEY A Well #: 2
County: GOVE Total Vertical Depth: 4299 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4289		200 SX
SURF	8.625	225		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2015 12:30 PM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: ED MONDERO Company: PICKRELL DRILLING Phone: (620) 793-2315

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 16 sx gel and 500 # hulls.
Shot perforations at 1888' and 950'. Perforations at 4178' - 4182' and 4289' - 4299'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/05/2015 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4250' and pumped 16 sx gel followed by 60 sx cement w/200 # hulls. Pulled tubing to 1925' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1025' and pumped 110 sx cement. Good circulation of cement. Pulled tubing out and topped off with 25 sx cement. Tied on to backside and squeezed with 50 sx cement. Shut in pressure 100 psi.

Perfs:


Top	Bot	Thru	Comments
4289	4299		
4178	4182		
2515	2515		
1711	1743		

Remarks: SWIFT CEMENT TICKET # 28598

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

CKM 12/2/15

NOV 09 2015

KCC WICHITA

Form CP-2/3

NOV 25 2015

RECEIVED