

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-20387-00-00
Spot: NENW Sec/Twnshp/Rge: 4-34S-2E
4290 feet from S Section Line, 3300 feet from E Section Line
Lease Name: FERGUSON Well #: 2
County: SUMNER Total Vertical Depth: 3800 feet

Operator License No.: 4699
Op Name: PHILLIPS OIL PROPERTIES INC.
Address: 733 N. BALTIMORE
DERBY, KS 67037

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2870		
PROD	5.5	3100		100 SX
SURF	8.625	231		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/10/2015 9:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: TROY PHILLIPS Company: PHILLIPS OIL PROPERTIES, INC. Phone: (316) 295-4335

Proposed Plugging Method: AS PER KCC RULES & REGS

KCC WICHITA
DEC 01 2015
RECEIVED

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 09/23/2015 7:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

CIBP SET @ 2870', SPOT 1/2 LB OF CEMENT ON TOP OF CIBP. TAGGED WITH WIRE LINE AT 2878'. PULLED TUBING TO 1900' AND CIRCUALTED 45 SX OF CEMENT LET THAT SET FOR A WHILE AND TAGGED TOP OF CEMENT WITH WIRE-LINE @ 2530'. PULLED TUBING TO 300' AND PERFORATED THERE, CIRCUALTED 98 SX OF CEMENT TO SURFACE, LET IT SET AND TOP DROPPED 60' SO TOPPED OFF AGAIN WITH 57 SX. PLUGGING COMPLETE. WELL(S) WERE PLUGGED DUE TO KCC'S RESPONSE TO LANDOWNER COMPLAINT. NO ORDER WAS ISSUED, OPERATOR RESPONDED AFTER NOV LETTERS WERE SENT OUT AND OPERATOR HAD A CONVERSATION WITH DIST. SUPERVISOR.

Perfs:


Top	Bot	Thru	Comments
2959	2962	TBG	
2817	2819	TBG	

Remarks: CONSOLIDATED OIL WELL SERVICES, LLC OUT OF EL DORADO KS. TICKET #48381.

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

CKM 12/2/15