

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-045-19102-00-00  
Spot: NESENESE Sec/Twnshp/Rge: 11-15S-20E  
1766 feet from S Section Line, 192 feet from E Section Line  
Lease Name: PEARSON Well #: OW2  
County: DOUGLAS Total Vertical Depth: 863 feet

Operator License No.: 32116  
Op Name: R.T. ENTERPRISES OF KANSAS, INC.  
Address: 120 SHORELINE DR  
LOUISBURG, KS 66053

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	0	0		0 SX
SURF	12	0		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/15/2015 12:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: LANCE TOWN Company: R.T. ENTERPRISES OF KANSAS, INC Phone: (913) 710-5400

Proposed Pump cement through pipe from bottom to surface.  
Plugging Method:

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE  
Date/Time Plugging Completed: 10/15/2015 12:00 PM KCC Agent: TAYLOR HERMAN

**Actual Plugging Report:**

**Perfs:**

WASHED DRILL PIPE DOWN TO 863' INSIDE THE SURFACE CASING. PUMPED CEMENT FROM 863' TO THE SURFACE. WATER STARTED COMING UP THROUGH CEMENT. DRILLED OUT CEMENT TO WATER ZONE AT 300'. PUMPED GEL INTO WATER ZONE AND LET SIT FOR A FEW DAYS. RAN DRILL PIPE DOWN TO 300' AND PUMPED CEMENT TO THE SURFACE. PULLED THE DRILL PIPE OUT AND HOOKED ON TO CASING AND SQUEEZED ADDITIONAL CEMENT. THE WELL HAD A SHUT-IN PRESSURE OF 500 POUNDS.

RECEIVED  
KCC DIST # 3  
NOV 24 2015  
CHANUTE, KS

TH

Remarks: THIS WAS A BREAK OUT WELL THAT THE OPERATOR WAS REQUIRED TO PLUG.

Plugged through: DP

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

CKM 12/2/15

KCC WICHITA CP-2/3

NOV 30 2015

RECEIVED