

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-195-21375-00-00  
Spot: NE Sec/Twnshp/Rge: 2-12S-25W  
1320 feet from N Section Line, 1320 feet from E Section Line  
Lease Name: HOBBS "D-P" Well #: 3  
County: TREGO Total Vertical Depth: 4220 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4219		200 SX
SURF	8.625	250		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/04/2015 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: PETE FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
DV Tool at 2153' w/400 sx cement.  
Perforations: 4088' - 4094'

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/05/2015 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4015' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 3104' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2162' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1189' and pumped 75 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 75 sx cement. Cement falling. Will let cement set and check on 11/05/2015.  
11/05/2015- Topped off casing with 30 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.

GPS: 39.04142 -100.06030

Perfs:


Top	Bot	Thru	Comments
4088	4094		

Remarks: QUALITY CEMENT TICKET # 1911

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

KCC WICHITA

NOV 25 2015

RECEIVED

CKM 12/2/15

CM

NOV 10 2015

Form CP-2/3