

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-21425-00-01
Spot: NWSESENE Sec/Twnshp/Rge: 2-12S-25W
2200 feet from N Section Line, 440 feet from E Section Line
Lease Name: HOBBS DP Well #: 5
County: TREGO Total Vertical Depth: 4180 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4175		200 SX
SURF	8.625	263		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2015 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TOMMY ATKINS Company: RITCHIE EXPLORATION Phone: (785) 216-0155

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls and 8 sx gel.
Shot perforations at 1235' and 255'.
Perforations at 3998' - 4001', 4078' - 4083' and 4098' - 4102'.
DV Tool at 2170' w/425 sx cement. Cement did not circulate.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/05/2015 12:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4050' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 3050' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2048' and pumped 75 sx cement. Pulled tubing to 1260' and pumped 8 sx gel followed by 100 sx cement. Good circulation of cement. Pulled tubing out. Tied on to casing and squeezed with 60 sx cement. Casing full. Good circulation of cement out the backside.

GPS: 39.03856 -100.05714

Perfs:


Top	Bot	Thru	Comments
4098	4102		LKC- J
4078	4083		LKC- I
3998	4001		LKC- F

Remarks: QUALITY CEMENT TICKET # 1915

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM 12/2/15
CM

NOV 10 2015

KCC WICHITA

Form CP-2/3

NOV 25 2015

RECEIVED