

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-29257-00-00
Spot: W2SESWNW **Sec/Twnshp/Rge:** 15-24S-18E
2970 feet from S Section Line, 4400 feet from E Section Line
Lease Name: MONFORT **Well #:** 2 I
County: ALLEN **Total Vertical Depth:** 890 feet

Operator License No.: 32073
Op Name: THOMPSON, JEROME A. DBA THOMPS
Address: 2260 N DAKOTA RD
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	825		115 SX
SURF	8.625	21		6 SX

Well Type: OIL **UIC Docket No:** **Date/Time to Plug:** 09/17/2015 12:00 AM
Plug Co. License No.: 33977 **Plug Co. Name:** E K ENERGY LLC
Proposal Rcvd. from: JEROME THOMPSON **Company:** **Phone:** (620) 363-1045

Proposed Plugging Method: wash 1 inch to bottom of well, pump 25 sacks of cement, pull 1 inch to 500 feet, pump 30 sacks of cement, pull 1 inch to 60 feet top off well, remove 1 inch. return next day top off whatever well has settled to surface.

Plugging Proposal Received By: **WitnessType:** NONE
Date/Time Plugging Completed: 09/17/2015 8:00 AM **KCC Agent:** RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe to 860'. Washed well. Pumped 30 sacks portland cement through the 1" pipe at TD. Pulled 1" pipe to 500'. Pumped 25 sacks cement through the 1" pipe at 500' to surface. Pulled 1" pipe out of the well and topped off the well with 5 sacks cement. A total of 60 sacks of portland cement was reported used to plug this well.

RECEIVED
KCC DIST #3
NOV 24 2015
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

District: 03

Signed

Ryan Duling
E.C.R.S.
(TECHNICIAN)

CKM 12/2/15

KCC WICHITA

NOV 30 2015

RECEIVED