

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23976-00-00
Spot: W2NW Sec/Twnshp/Rge: 32-16S-24W
3931 feet from S Section Line, 4583 feet from E Section Line
Lease Name: DUBBS 3-32 Well #: E
County: NESS Total Vertical Depth: 4575 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4254		WITH 2 SX CMT
DVT	5.5	2288		
PROD	4.5	4574	0	WITH 90 SX CMT
SURF	8.625	311		WITH 170 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2015 10:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: MORRIS SMITH Company: TRANS PACIFIC OIL Phone: (316) 262-3596

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP GEL THEN 35 SX CMT & 150# HULLS. PULL TBG TO 1500' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2015 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4254' WITH 2 SX CMT. RUN TBG TO 2288' & PUMPED 170 SX CMT & 400# HULLS. CMT CIRCULATED. PULLED TBG TO 320' & CIRCULATED CMT OUT OF CASING. SHOT CASING AT 290' & PUMPED 60 SX CMT DOWN BACKSIDE & CIRCULATED OUT CASING.

Perfs:

Top	Bot	Thru	Comments
4519	4522		

KCC WICHITA
NOV 23 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

CKM 12/2/15

District: 01

Signed *Michael Maier*
SR (TECHNICIAN)

RECEIVED
NOV - 5 2015
KCC DODGE CITY *MP*