

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-001-20842-00-01  
Spot: NESWSE Sec/Twnshp/Rge: 29-26S-20E  
670 feet from S Section Line, 1805 feet from E Section Line  
Lease Name: CAMPBELL Well #: 1-14  
County: ALLEN Total Vertical Depth: 843 feet

Operator License No.: 4485  
Op Name: VERDE OIL COMPANY  
Address: 1020 NE LOOP 410 STE 555  
SAN ANTONIO, TX 78209

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	816		100 SX
SURF	6.25	20		5 SX

Well Type: EOR UIC Docket No: E18163.10 Date/Time to Plug: 09/15/2015 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: JEFF DALE Company: Phone: (620) 754-3800

Proposed Plugging Method: Run tubing to PBTD. Circulate cement to surface. Pull tubing & fill displacement from surface. Cut off casing strings below plow depth.

Plugging Proposal Received By: WitnessType: NONE  
Date/Time Plugging Completed: 09/15/2015 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe inside the 2.875" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2.875" casing from TD to surface. Pulled the 1" pipe out of the well and topped the well off with cement. A total of 26 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
816	842		

RECEIVED  
KCC DIST #3  
NOV 24 2015  
CHANUTE, KS  
RD

Remarks:

Plugged through: TBG

District: 03

Signed

E.C.R.S.  
(TECHNICIAN)

CKM 12/2/15

UIC

Form CP-2/3

KCC WICHITA

NOV 30 2015

RECEIVED