

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-21265-00-01
Spot: SWSENE Sec/Twnshp/Rge: 34-17S-27W
2955 feet from S Section Line, 1017 feet from E Section Line
Lease Name: WHIPPLE Well #: 34-8
County: LANE Total Vertical Depth: 4700 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 400 N WOODLAWN ST, STE 18
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2100		
DVT		2174		WITH 500 SX CMT
PROD	4.5	4702	0	WITH 700 SX CMT
SURF	8.625	298		WITH 185 SX CMT

Well Type: SWD UIC Docket No: D24929.0 Date/Time to Plug: 11/10/2015 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE FRITZLER Company: FRITZLER Phone: (316) 262-2502

Proposed
Plugging
Method:

PUMP PERFS WITH 50 SX CMT & 200# HULLS. CIRCULATE TO SURFACE. PULL TBG & TOP OFF.

Plugging Proposal Received By: LARRY HARRIS Witness Type: NONE
Date/Time Plugging Completed: 11/10/2015 11:00 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

RUN TBG TO 1520' & PUMPED 130 SX CMT & 200# HULLS. CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 300#

Perfs:

Top	Bot	Thru	Comments
1615	1665		

KCC WICHITA
NOV 23 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

CKM 12/2/15

District: 01

Signed

Larry D. Harris EC RS
(TECHNICIAN)

RECEIVED
NOV 18 2015
KCC DODGE CITY

SA