

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-20964-00-00
Spot: SWNENE Sec/Twnshp/Rge: 31-29S-18W
985 feet from N Section Line, 962 feet from E Section Line
Lease Name: EDMONSTON Well #: 1
County: KIOWA Total Vertical Depth: 5050 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4740		WITH 2 SX CMT
PROD	4.5	5049	2477	WITH 200 SX CMT
SURF	8.625	575		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/05/2015 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JEFF WERTH Company: H-D OILFIELD SERVICE Phone: (620) 388-6143

Proposed Plugging Method: CIBP @ 4740' WITH 2 SX CMT. PLUG AT 1180' WITH 15 SX GEL & 50 SX CMT. PLUG AT 620' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/05/2015 3:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4740' WITH 2 SX CMT. 1ST PLUG AT 1180' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 620' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED BUT WAS SLOWLY FALLING. 11/6/15: THE CMT PLUG FELL APP. 3 1/2 SECONDS FROM SURFACE. 11/11/15: DUMPED APP. 2 1/2 YARDS OF READY-MIX DOWN 8 5/8".

Perfs:

Top	Bot	Thru	Comments
4792	4796		

KCC WICHITA
NOV 23 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed [Signature]
SA (TECHNICIAN)

CKM 12/2/15

RECEIVED
NOV 18 2015
KCC DODGE CITY