

1 040363

11-22

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,748 - 0000

NE SW SE, SEC. 1, T 25 S, R 15 W/E
990 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Lease Name Waters Well # 1

Operator: Falcon Exploration, Inc.
Name & Address: 125 North Market, Suite 1075
Wichita, KS 67202

County Stafford 146.74

Well Total Depth 4515 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 322

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Plains Inc. License Number 4072

Address P.O. Box 346, Ness City, KS 67560

Company to plug at: Hour: 11 a.m. Day: 22 Month: 11 Year: 19 89

Plugging proposal received from Max Parsons

(company name) Falcon Exploration, Inc. (phone) 913-625-6904

were: 4 1/2" at 4362' PBD 4309' Perfs at 4220-4225' Elevation 2006' GL

1st plug sand back to 4175' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45 p.m. Day: 22 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4175' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 50 psi.

11-28-89
NOV 28 1989

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1840' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-6-89
INV. NO. 26630

Signed Stephen J. Pfeifer (TECHNICIAN)