

To: 1-120408
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-11 121 R
API NUMBER 15- 185-20,930 - 0000
NW NE NW, SEC. 1, T 25 S, R 15 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4419

Operator: Bear Petroleum
Name & Address Box 438
Haysville, KS 67060

4950 feet from S section line
3630 feet from E section line

Lease Name Waters Well # B-1
County Stafford 143.00

Well Total Depth 4400 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 471

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1:30 p.m. Day: 11 Month: 4 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4398' PBSD 4398' Perfs at 4277-83' Elevation 2014' KB

1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4 p.m. Day: 11 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4225' and dumped 5 sx cement
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1834' of 5 1/2" casing.

INVOICED

DATE 4-24-90 4-8-90

INV. NO. 27928

Signed Duane Rankin
(TECHNICIAN)