

1 120848

10-20

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,486-0001
SE SE NW, SEC. 14, T 25 S, R 15 W/EX
2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061
Operator: Oil Producers of Kansas Inc.
Name & Address: P.O. Box 8647
Wichita, KS 67208

Lease Name Wilson B Well # 1
County Stafford 139.75
Well Total Depth 4300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor DS&W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 2:30 p.m. Day: 20 Month: 10 Year: 19 93

Plugging proposal received from Joe Strube
(company name) DS&W Well Servicing, Inc. (phone) 316-587-3361

were: 4 1/2" at 4297' w/125 sx cement, PBSD 4265', Perfs at 4244-50, 4214-24'
1st plug sand 4 1/2" casing back to 4160' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 4 p.m. Day: 20 Month: 10 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4160' and dumped 4 sx cement on
top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 250 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 150 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Pumping pressure 0-600 psi and shut in 100 psi.

RECEIVED STATE CORPORATION COMMISSION

10-28-93 OCT 28 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2079' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE NOV 05 1993
INV. NO. 39138

Signed Dennis Roush (TECHNICIAN)