

1041313
TO: STATE CORPORATION COMMISSION

8-2)

API NUMBER 15-185-23,010-0000
NE SE NW SEC. 11, T 25 S, R 15 W

CONSERVATION DIVISION - PLUGGING SECTION 3630 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME COON FIELD WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD 141.05

OPERATOR LICENSE # 8061 WELL TOTAL DEPTH 4340' FEET

OPERATOR: OIL PRODUCERS INC. OF KANSAS PRODUCTION CSG: SIZE 4 1/2 " FEET 4339

NAME AND ADDRESS PO BOX 8647 2400 N WOODLAWN #115 SURFACE CASING: SIZE 8 5/8" FEET 280'

ADDRESS WICHITA, KS 78208-8674

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR D.S. & W WELL SERVICING, INC LICENSE NUMBER 6901

ADDRESS PO BOX 231, CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 12:15 PM DAY: 21 MONTH: 08 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KENT STRUBE

(COMPANY NAME) D.S. & W WELL SERVICING, INC (PHONE) 316-587-3361 9-1-98

WERE: PERFS AT 4246 TO 4278 PBSD AT 4295'

1ST PLUG SANDED BACK TO 4175' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THRU DUMP BAILER.

SPOT PLUGS THROUGH 4 1/2" CASING LOADED HOLE WITH GEL.

2ND PLUG AT 980' WITH 50 SX CEMENT, 3RD PLUG AT 310' WITH 50 SX CEMENT,

4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 1:15 PM DAY: 21 MONTH: 08 YEAR: 1998

ACTUAL PLUGGING REPORT _____

1ST PLUG SANDED BACK TO 4175' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THRU DUMP BAILER.

SPOT PLUGS THROUGH 4 1/2" CASING LOADED HOLE WITH GEL.

2ND PLUG AT 980' WITH 50 SX CEMENT, 3RD PLUG AT 310' WITH 50 SX CEMENT,

4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. 2090' OF 4 1/2" CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (I) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer
(TECHNICIAN) FORM CP-2/3

INVOICED
SEP 04 1998
DATE _____
INV. NO. 51265

RECEIVED
MAY 12 1998
1:5