

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-185-10335-0000
 API NUMBER 6-15-59
 LEASE NAME Grunder

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1
330 Ft. from S Section Line
660 Ft. from E Section Line
 SEC. 11 TWP. 25 RGE. 15 (S) or (W)
 COUNTY Stafford

LEASE OPERATOR Redstone Oil & Gas Company
 ADDRESS 8235 Douglas Ave. Suite 1050 Dallas, Tx
 PHONE#(214) 378-0202 OPERATORS LICENSE NO. 30040

Date Well Completed 12-11-59

Character of Well Oil

RECEIVED
 KANSAS CORPORATION COMMISSION

Plugging Commenced 7-20-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-22-94

The plugging proposal was approved on 6-27-94 AUG 05 1994 8-5-94 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filled? old well If not, is well log attached?

CONSERVATION DIVISION
 WICHITA, KS

Producing Formation Mississippi Depth to Top 4226 Bottom 4232 T.D. 4236

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing	water	0	292	8 5/8	292	None
Mississippi	oil	0	4236	5 1/2	4236	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
150 # Hulls with 50 sks. cmt. followed w/ 200# Hulls in 7 sks. gel. Followed w/ 50 sks. cmt. down 2 7/8 Tbg. from 1000'. Pump 85 sks. cmt. from 600'. Pull Tbg. pump down 5 1/2" Csg. filling to surface. Tag cmt. 27'. Weld plate in 8 5/8 Csg. 5" below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Chase Well Service License No. 6123

Address P. O. Box 355 Great Bend, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Redstone Oil & Gas Company

STATE OF Texas COUNTY OF Dallas, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wayne Roberts

(Address) P.O. Box 278 Woodward OK

SUBSCRIBED AND SWORN TO before me this 2nd day of August, 19 94

Joseph Vincent Casper
 Notary Public

My Commission Expires: My Commission Expires May 10, 1997