


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 20 Twp. 25S Rge. (E) 15 (W)
Location as "NE/CNW*SW*" or footage from lines C NE SE
Lease Owner Chief Drilling Co., Inc.
Lease Name Beckerdite Well No. 1
Office Address P.O. Box 797, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-4- 19 62
Application for plugging filed 1-4- 19 62
Application for plugging approved 1-4- 19 62
Plugging commenced 1-4- 19 62
Plugging completed 1-4- 19 62
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Jr., Route #1, Stafford, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4461 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand and Gravel		0	270'	8-5/8"	270'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1/3 sack hulls, set wooden plug at 240' with 20 sacks cement thru drill pipe
1/3 sack hulls, set wooden plug at 35' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1962
CONSERVATION DIVISION
Wichita

1-15-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address P.O. Box 797, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
V. Richard Hoover, President of Chief Drlg. Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) V. Richard Hoover
Box 797, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of January, 19 62

My commission expires June 18, 1963
Dorothy B. John Notary Public.



15-185-01131-0000

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

Beckerdite #1
C NE SE Sec. 20-25S-15W
Stafford County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: Dec. 22, 1961
Completed: Jan. 4, 1962

Casing Record: 8-5/8" surface pipe at 270' with 250 sack cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand	0	165	2025' Gr.
Shale	165	270	2027' H.F.
Shale & Sand	270	680	2030' K.B.
Redbed and Shale	680	998	
Anhydrite	998	1015	
Shale & Shells	1015	1900	
Shale & Lime	1900	3655	
Lime	3655	3679	
Shale & Lime	3679	3841	
Lime	3841	4117	
Lime & Shale	4117	4278	
Chert	4278	4319	
Sand & Shale	4319	4383	
Lime and Chert	4383	4461	
Total Depth	4461		

<u>FORMATION TOPS</u>			
	<u>Sample</u>	<u>Log</u>	
Anhydrite (drillers)	998		
Heebner	3679	3678	
Toronto	3700	3698	
Douglas	3717	3717	
Brown Lime	3833	3833	
Lansing	3841	3844	
Base Kansas City	4117	4117	
Mississippi	4278	4277	
Sand	4319	4319	
Viola	4383	4383	
Rotary Total Depth	4461	4461	

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NE SE Sec. 20-25S-15W, Stafford County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 12th day of January, 1962

Dorothy B. John
Dorothy B. John, Notary Public

My commission expires: June 18, 1963

1-15-62
NOTARY PUBLIC
WICHITA, KANSAS