

15-159-30099-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rice County, Sec. 12 Twp. 18S Rge. 10W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW SW NW

Lease Owner Alpine Oil & Royalty Co., Inc.

Lease Name Tena Hohl Well No. 1

Office Address 800 Bitting Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed July 28, 1965 19

Application for plugging filed February 10, 1972 19

Application for plugging approved February 11, 1972 19


Plugging commenced February 24, 1972 19

Plugging completed February 28, 1972 19

Reason for abandonment of well or producing formation Non-productive in commercial quantities

If a producing well is abandoned, date of last production January 2, 1972 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Arbuckle Depth to top 3266' Bottom 3285' Total Depth of Well 3285' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Oil	3266'	3285'	8-5/8"	217'	Cemented
				5-1/2"	3270'	2481'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with sand from 3285 feet to 3270 feet.
Ran 5 sacks of cement from 3270 feet to 3240 feet. Pumped 3 sacks of hulls, 20 sacks of gell mud & 75 sacks of cement to plug well.

RECEIVED
STATE CORPORATION COMMISSION
MAR 3 1972
CONSERVATION DIVISION
Wichita, Kansas
03-03-72

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address Box 156, Ellinwood, Kansas 67526

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Jon T. Williams, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jon T. Williams, Jr.
800 Bitting Building, Wichita, Kansas 67202
(Address)

Sworn to before me this 2nd day of March, 1972



Vashti Bell
Notary Public.

My commission expires September 14, 1973

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION
MAR 3 1972
CONSERVATION DIVISION
Wichita, Kansas

TENA HOHL #1
NW SW NW SECTION 12-18S-10W
RICE COUNTY, KANSAS

COMMENCED: JULY 19, 1965
COMPLETED: JULY 19, 1965

OPERATOR - ALPINE OIL & ROYALTY Co., INC.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	217	CLAY AND SAND	RAN 7 JOINTS OF 8-5/8" CASING, SET @ 217' w/100 BAGS CEMENT.
217	270	CLAY AND SAND	
270	485	RED BED	
485	495	ANHYDRITE	
495	1230	RED BED AND SHALE	
1230	2580	SHALE AND LIME	
2580	3285	LIME	
3285	TD		RAN 103 JOINTS OF 5" CASING, SET @ 3285' w/100 BAGS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE NW SW NW SECTION 12-18S-10W, RICE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 22ND DAY OF JULY, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC

