


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stafford County. Sec. 36 Twp. 25S Rge. (E) 15 (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Arvel C. Smith
Lease Name Smith Well No. 1
Office Address 569 Stratford Road, Wichita 6, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 20, 19 60
Application for plugging filed November 20, 19 60
Application for plugging approved November 20, 19 60
Plugging commenced November 20, 19 60
Plugging completed November 20, 19 60
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill LaKamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	329'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with heavy rotary mud to 300 ft. Bridge at 300 ft. with 20 sacks cement on bridge. Hole filled with heavy rotary mud to 30 ft. Bridge at 30 ft. with 10 sacks Cement on bridge. Rat hole filled with heavy rotary mud & capped with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 23 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor White & Ellis Drilling, Inc. - License #209
Address Box 448 - El Dorado, Kansas

STATE OF Kansas COUNTY OF Butler, ss.
Ernest Sifford, employee of Contractor ~~(employee of owner) or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
Box 448 - El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of November, 19 60

L. B. Auer

My commission expires September 26, 1964 Notary Public.



8 3/8

329' Cemented
w/275 sacks

T.D.	4600'
Kelly Bushing Measurement	5' above ground level.
FORMATION	DEPTH
Soil	0-5
Sand	80
sd. Clay	145
Clay	329
Red rock	975
Anhydrite	990
Anhydrite & Shale	1210
Shale & Shells	1875
Anhydrite	1905
Lime & Shale stks.	2020
Lime	2100
Lime & Shale stks.	2260
Shale & Lime, sd.	2400
Shale & Lime stks.	2570
Lime & Shale stks.	3683
Lime	3702
Shale & Lime	3805
Br. Lime	3814
Shale & Lime	3832
Lime	4110
Lime & Shale	4279
Lime	4315
Lime & Shale	4368
Lime	4503
Shale & Lime	4546
Shale & Sand	4569
Lime	4600

TOPS

Heobner	3654
Toronto	3675
Douglass	3696
Brown Lime	3806
Lansing	3833
Base Kansas City	4113
Mississippi Chert	4284
Kinderhook	4296
Viola	4354
Simpson	4504
Arbuckle	4558

Dry Hole
Plugged & Abandoned

STATE OF KANSAS)
) ss
COUNTY OF BUTLER)

I hereby certify that the foregoing
is a true and correct copy of the Well Log
for the Smith No. 1 well completed
November 20, 1960.

Howard E. Russell
Howard E. Russell
Vice President

Subscribed and sworn to, before the under-
signed, a Notary Public, in and for the
County and State aforesaid, this 22nd day
of November, 1960.

L. B. Auer
L. B. Auer
Notary Public

My Commission Expires September 26, 1964.

RECEIVED
STATE CORPORATION COMMISSION
11-23-60
NOV 23 1960

CONSERVATION DIVISION
Wichita, Kansas