


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

EDWARDS County, Sec. 1 Twp. 25S Rge. 16 (E) W (W)
Location as "NE/CNW/SE" or footage from lines C NW NE
Lease Owner SIERRA PETROLEUM CO., INC.
Lease Name W. H. DUTTON Well No. 1
Office Address 208 PETROLEUM BUILDING, WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed NOVEMBER 19, 1962
Application for plugging filed NOVEMBER 19, 1962
Application for plugging approved NOVEMBER 19, 1962
Plugging commenced NOVEMBER 19, 1962
Plugging completed NOVEMBER 19, 1962
Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. LOCKAMP, STAFFORD, KANSAS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4220 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>SAND & SHALE</u>	<u>SURFACE CSG.</u>	<u>-0-</u>	<u>245'</u>	<u>8-5/8"</u>	<u>245'</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED: Filled hole with heavy mud from 4220' up to 240'. Bridged using Halliburton Plug, 1/4 sk. hulls, 20 sx. cement through drill pipe.
Filled hole to 40' with heavy mud. Bridged using Halliburton Plug, 1/4 sk. hulls, 15 sx. cement to cellar zero.
Job completed 7:45 p.m. 11-19-62.
NOV 23 1962
STATE CORPORATION COMMISSION
Wichita, Kansas
11-26-62

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SIERRA PETROLEUM CO., INC.
Address 208 PETROLEUM BUILDING, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
G. T. HONAKER, DRILLING SUPERINTENDENT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. T. Honaker G. T. HONAKER, DRG. SUPT.
BOX 232, RUSSELL, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 23RD day of NOVEMBER, 1962

My commission expires 10-17-63

Leroy Dietz
Notary Public.



SIERRA PETROLEUM CO., INC. - Operator

T. D.: 4220'
Elev.: 2062' K.B.

W. H. DUTTON #1
C NW NE
Sec. 1-25S-16W
Edwards County, Kansas

Commenced: 11-7-62
Completed: 11-19-62

Casing:
8-5/8" Set at 245'

Cement:
with 200 sx cement

FORMATION	DEPTH
Sand	210
Shale	380
Red Bed	1010
Anhydrite	1025
Shale & Shells	1615
Shale & Lime	1990
Shale & Sand	2148
Shale & Lime	3305
Lime	3450
Lime & Shale	3725
Lime	4220

11-26-62

NOV 26 1962
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C.T. Hanaker
Drilling Superintendent

Subscribed and sworn to before me this 23rd day of November, 1962.

Gerry Dietz
Notary Public

My commission expires: 10-17-63