

15-047-00079-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form C.P. 1

WELL PLUGGING RECORD

Give All Information Completely
State Required Methods of
Mailing Returns Report to
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217



Locate well correctly on above
Section Plat

Edwards County, Sec 3 Twp. 25 Rge. 16 (E) (W)
Location as "NE/SW/SE" or footage from lines C SL NW/4
Lease Owner Raymond Oil Co., Inc.
Lease Name Breitenbach #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 5/11/74 19
Plugging completed 5/16/74 19
Reason for abandonment of well or producing formation depleted
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservattou Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4408 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	409	none
				4 1/2"	4407	2299'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Halliburton pumped 2 loads water to kill well and put plug container on, pumped 25 sacks cement and pumped plug to 3500', Checked hole, shot pipe at 3412', 3271', 3140', 2998', 2900', 2810', 2708', 2604', 2503', 2405', 2308', pulled 71 joints. Pumped 2 sacks hulls, 10 sacks gel and 100 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1974
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor (If additional description is necessary, see BACK of this sheet)
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)

Subscribed and sworn to before me this 16th day of May 1974

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

Handwritten mark or signature.

15-047-00079-0000

RECEIVED
STATE CORPORATION COMMISSION
APR 4 - 1974
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

No. 1 Breitenbach
Chief Drilling Co. - Hudson Oil Co., etal.
Box 97
Great Bend, Kansas

Elevation: 2075 DF
2073 GRD
2078 KB

No. 1 Breitenbach
Approx. CSL NW/4 Sec. 3-25-16W
Edwards County, Kansas

Contractor: Chief Drilling Co., Inc.
Rotary: 0-4407'

Casing Record: Set 8 5/8" @ 409' W/350 sacks.
Set 4 1/2" @ 4407' W/150 sacks.

Formation	Top	Bottom	Formation	Tops & Minus
Sand, Shale & Clay	0	410	Anhydrite	1046 (+1032)
Shale & Redbed	410	450	Heebner	3681 (-1603)
Shale & Sandy Redbed	450	1046	Toronto	3701 (-1623)
Anhydrite	1046	1056	Brown Lime	3823 (-1745)
Shale & Shells	1056	1795	Lansing	3832 (-1754)
Lime & Shale	1795	2215	Base K.C.	4109 (-2031)
Lime	2215	2450	Cherokee Shale	4252 (-2174)
Lime & Shale	2450	2725	Mississippi	4270 (-2192)
Shale & Lime	2725	3710	Kinderhook Sand	4320 (-2242)
Shale	3710	3823	Viola	4388 (-2310)
Limestone	3823	4109	Total Depth	4408 (-2330)
Broken Lime & Shale	4109	4252		
Shale	4252	4270		
Chert	4270	4304		
Shale	4304	4320		
Sand	4320	4330		
Shale	4330	4388		
Chert & Lime	4388	4408		
Total Depth		4408		

STATE OF KANSAS)
COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of Drillers' Log of well drilled in approximately CSL NW/4 Section 3-25-16W, Edwards County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.
V. Richard Hoover
V. Richard Hoover, President

Subscribed to and sworn to before me this 14th day of August, 1958

Norris Taylor
Norris Taylor, Notary Public

My Commission Expires:
May 19, 1962