

1060202

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-20,664-0000
NE SE SE SEC. 3, T 25 S, R 15 W

CONSERVATION DIVISION - PLUGGING SECTION 4290 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4950 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BARSTOW "B" WELL # 1

TECHNICIAN'S PLUGGING REPORT

4/26

COUNTY STAFFORD

138.45

OPERATOR LICENSE # 5298

WELL TOTAL DEPTH 4260 FEET

OPERATOR: GOULD OIL, INC.

PRODUCTION CSG: SIZE 4 1/2" @ 4255' WITH 150 SX

NAME AND 3500 N ROCK ROAD, BLDG 800-A

SURFACE CASING: SIZE 8 5/8" @ 242' WITH 250 SX

ADDRESS WICHITA, KS 67226

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR PLAINS INC. LICENSE NUMBER 4072

ADDRESS PO BOX 346 NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 5:00 PM DAY: 26 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DARIN

(COMPANY NAME) PLAINS INC. (PHONE) 785-798-3995

WERE: PERFS AT 4148-58, 4186-89.

1ST PLUG PUMP 20 SX CEMENT AND 200# HULLS TO 4000'. 2ND PLUG AT 990' WITH 50 SX CEMENT.

3RD PLUG AT 270' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 7:15 PM DAY: 26 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT 5-8-00

1ST PLUG PUMP 20 SX CEMENT AND 200# HULLS TO 4000'. 2ND PLUG AT 990' WITH 50 SX CEMENT.

3RD PLUG AT 270' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

MAY 8 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1800' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED
SIGNED
DATE 5/9/00
WEL. NO. 61692

Michael J Maier
(TECHNICIAN)

FORM CP-2/3

CONSERVATION DIVISION
Wichita, Kansas

(R)