

1 050569

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,209-0000

NW SE SE, SEC. 2, T 25 S, R 15 ^(W) _(E)

990 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6393

Lease Name Wilson-Page Well # 3

Operator: Brougher Oil, Inc.

County Stafford (Arbuckle)

Name & Address P. O. Box 1367

Well Total Depth 4470 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 358

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Mohawk Drilling, Inc. License Number 6394

Address Box 1362, Great Bend, KS 67530

Company to plug at: Hour: 2:00 am Day: 9 Month: July Year: 19 85

Plugging proposal received from Wilbur Cotton

(company name) Brougher (phone) 316-793-5610

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2031'
Anhydrite 1020

1st plug at 1020' with 50 sx cement

2nd plug at ^{solid bridge} 360' with 40 sx cement

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:45 am Day: 9 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1020' with 50 sx cement, 2nd plug at 360' with 40

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate ra thole with 10 sx cement, 6th plug to

circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

1111 11 1985 7-11-85

Remarks: Used 60/40 Pozmix 6% gel by Halliburton

(if additional description is necessary, use BACK of this form.)
Wichita, Kansas

INVOICED

DATE 7-15-85

INV. NO. 8935

Signed Richard W. Lacey
(TECHNICIAN)

7-9 AUG 14 1985