

1100370

TO: STATE CORPORATION COMMISSION

API NUMBER 15-055-20,370-0000  
C SW NW NE SEC. 21, T 26 S, R 31 W

CONSERVATION DIVISION - PLUGGING SECTION 1250 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2640 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME KLEYS TEUBER-GILLEN WELL # A-1

TECHNICIAN'S PLUGGING REPORT

COUNTY FINNEY 89.38

OPERATOR LICENSE # 31566

WELL TOTAL DEPTH 2750 FEET

OPERATOR: BENCHMARK OIL & GAS PRODUCTION CSG: SIZE 4 1/2" @ 2725' WITH 350 SX

NAME AND 1515 ARAPAHOE ST., SUITE 580 SURFACE CASING: SIZE 7" @ 600' WITH 300 SX

ADDRESS DENVER, CO 80202-3150

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING LICENSE NUMBER 31151

ADDRESS RT 1 BOX 49 BA TYRONE, OK 73951

COMPANY TO PLUG AT: HOUR: 9:30 PM DAY: 28 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING (PHONE) 316-624-7455

WERE: PERFS AT 2652-60

1ST PLUG SPOT 100# HULLS AND 20 SX CEMENT AT 2652-2452'. CIRCULATE HOLE.

2ND PLUG SPOT 50 SX CEMENT AT 800'. 3RD PLUG SPOT 25 SX CEMENT AT 300'.

4TH PLUG SPOT 10 SX CEMENT AT 40' TO 0'.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 28 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT \_\_\_\_\_

1ST PLUG SPOT 100# HULLS & 20 SX CEMENT AT 2652-2452. CIRCULATE HOLE.

2ND PLUG SPOT 50 SX CEMENT AT 800'. 3RD PLUG SPOT 25 SX CEMENT AT 300'.

4TH PLUG SPOT 10 SX CEMENT AT 40' TO 0'.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 6 2000

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 825' OF 4 1/2" CASING. Conservation Division  
Wichita, Kansas

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED SIGNED Gary Winters  
(TECHNICIAN) FORM CP-2/3  
DATE 7/10/00  
WV. NO. 1060026

(Handwritten initials and a circled 'R')