

15-055-20440-0000

To: 1051926. 5-16
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Docket #D-20,497

SE NW NE, SEC. 3, T 26 S, R 31 W/E

4030 feet from S section line

1390 feet from E section line
Irrigated Land

Lease Name Development Well # 1

County Finney 162.47

Well Total Depth 4999 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 655

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058

Operator: American Warrior, Inc.

Name & Address P.O. Box 399

Garden City, KS 67846

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address

Company to plug at: Hour: 10:30 a.m. Day: 16 Month: 5 Year: 1995

Plugging proposal received from Kevin Wiles

(company name) American Warrior, Inc. (phone) 316-275-2963

logs: 5 1/2" at 4995' w/325 sx cement, PBTD 3410', Perfs at 3292-3306, 2637-2645'

DV at 3377' w/475 sx cement.

1st plug at 2672' with 15 sx gel and 25 sx cement, 2nd plug at 1812' with 25 sx cement,

3rd plug at 760' with 25 sx cement, 4th plug at 60' with 10 sx cement,

5th plug pump down 8 5/8" X 5 1/2" annulus with 150 sx cement.

Plugging Proposal Received by Richard M. Saoy (TECHNICIAN)

RECEIVED MAY 17 1995 5-17-95

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:15 p.m. Day: 16 Month: 5 Year: 1995

ACTUAL PLUGGING REPORT Pumped plugs through tubing:

1st plug at 2672' with 15 sx gel and 25 sx cement,

2nd plug at 1812' with 25 sx cement,

3rd plug at 760' with 25 sx cement,

4th plug at 60' with 10 sx cement,

5th plug pumped down 8 5/8" X 5 1/2" annulus with 150 sx cement. Maximum pressure 250 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 5-22-95

Signed Richard W. Lacy (TECHNICIAN)

INV. NO. 42850