

To: 1 090310
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-11 API NUMBER 15- Drilled 6/12/81 15-069-2023-0000

SW SW NW, SEC. 20, T 26 S, R 29 W/E

2970 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4868
OK

Lease Name Monger Well # 2

Operator: Asher Associates, Inc.

County Gray 165.26

Name & Address 2350 E. Williamette Lane, #310

Well Total Depth 5085 feet

Greenwood Village, CO 80121

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 450

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 8:30 a.m. Day: 9 Month: 8 Year: 19 93

Plugging proposal received from Richard Smith

(company name) Murfin Drilling Company, Inc. (phone) 316-267-3241

work: 4 1/2" at 5069' w/125 sx cement. Perfs at 4960-71', Packer stuck at 4590'

1st plug set CIBP at 4500',

Perforate at 1000',

2nd plug pump 160 sx cement down casing,

3rd plug pump 160 sx cement down backside.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 p.m. Day: 11 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT 8/9 Set CIBP at 4500', loaded casing to test-well took 50 bbl, well on vacuum. 8/10 Ran free point. Pipe stuck at 520' from surface. Ran tubing and packer to isolate leak. Found at 1280' from surface. 8/11 Set CIBP at 1100'. Perforated casing at 975'. Pumped in 160 sx cement down 4 1/2". Shut in pressure 200 psi. Hooked onto backside and pumped in 165 sx cement. Shut in 0 psi and maximum pressure 400 psi.

RECEIVED STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery. 8-3-93 AUG 13 1993

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE AUG 18 1993

Signed _____ (TECHNICIAN)

INV. NO. 38370

8-11 OCT 13 1993 MAR 15 1994