

1030238

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-057-20,105-0000

W/2 W/2 SE/4 SEC. 22 T 26 S, R 24 W/2
1320 feet from N SE Corner of section line
2310 feet from W SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Maxwell "B" Well # 1

Operator: Pickrell Drilling Company

County Ford

Name & Address 110 North Market, Suite 205

Well Total Depth 5110 166.08 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 574

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 1:30 pm Day: 3 Month: August Year: 1984

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 4 1/2" set at 5102' Perfs 4995-4999' PBTB 5047

1st plug sand back to 4950' and dump 4 sx cement on top of sand

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump an additional 150 sx cement.

Plugging Proposal Received by Steve Quinlan (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:50 pm Day: 3 Month: August Year: 1984

ACTUAL PLUGGING REPORT 4 1/2" set at 5102' Perfs 4995-4999' PBTB 5047'

1st plug sanded back to 4950' and dumped 4 sx cement on top of sand through bailer

2nd plug squeezed well with 3 sx hulls, 14 sx gel and 200 sx cement.

Maximum pressure 1300 psi and shut in pressure 600 psi

RECEIVED STATE CORPORATION COMMISSION 8-7-84 AUG 07 1984

CONSERVATION DIVISION Wichita, Kansas

Remarks: They recovered 2800' of 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied. (If additional description is necessary, use BACK of this form.)

observe this plugging.

Signed Steve Quinlan (TECHNICIAN)

DATE 8-14-84

INV. NO. 3078