

6-5 15-185-11100-0000

To: 1 120574  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
206 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 10/2/61  
NW NE NW, SEC. 15, T 25 S, R 15 W/E  
4950 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134  
Operator: Graham-Michaelis Corporation  
Name & Address P.O. Box 247  
Wichita, KS 67201

Lease Name Wiles Well # 3  
County Stafford 136.82  
Well Total Depth 4210 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4:30 p.m. Day: 5 Month: 6 Year: 19 91

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4208' w/150 sx cement, PBTB 4184', Perfs at 3826-30', DV @ 2741' w/175 sx cem.  
TOC 2000'

1st plug sand back to 3775' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:45 p.m. Day: 5 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3775' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.  
Pumping pressure 0-400 psi and shut in 200 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
6-13-91  
JUN 17 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1900' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 6-20-91

Signed Glenn Barlow  
(TECHNICIAN)

INV. NO. 32206