

6-5 15-185-11099-0000

To: 1 120573
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 10/22/60
SE SW NW, SEC. 15, T 25 S, R 15 W
2970 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134
Operator: Graham-Michaelis Corporation
Name & Address: P.O. Box 247
Wichita, KS 67201

Lease Name Wiles Well # 2
County Stafford 139.42
Well Total Depth 4290 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 5 Month: 6 Year: 1991

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4288' w/200 sx cement, PBD 3945', Perfs at 3922-26'

1st plug sand 5 1/2" casing back to 3870' and dump 5 sx cement on top of sand through bailer,
2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 5 Month: 6 Year: 1991

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3870' and dumped 5 sx cement on
top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-150 psi and shut in 50 psi.

RECEIVED
STATE CORPORATION COMMISSION
6-13-91
JUN 13 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 300' of 5 1/2" casing
If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 6-20-91

Signed Dave Rankin (TECHNICIAN)

INV. NO. 32205