

1 051397

1-2815-185-11098-0008 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19- Docket #D-10,450

C SW SW, SEC. 15, T. 25 S, R 15 W/E

660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Hart Well # A-3

Operator: Oil Producers, Inc. of Kansas
Name & Address: P.O. Box 8647
Wichita, KS 67208

County Stafford 140.92

Well Total Depth 4336 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 299

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering Inc. License Number 5111

Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 28 Month: 1 Year: 19 91

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering Inc. (phone) 316-792-2506

were: 5 1/2" at 4335', PBTD 4175', Perfs at 3930-36'

1st plug sand back to 3880' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

1-31-91
JAN 31 1991
Richard Lacey
(TECHNICIAN)
Wichita, Kansas

Plugging Proposal Received by Richard Lacey

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:20 p.m. Day: 28 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3880' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Maximum pressure 700 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2720' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE FEB 13 1991
INV. NO. 30714

observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)