

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-20,367-0000

C SE SW, Sec. 8, T 25 S, R 15 W/X

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Cotton Well # 1

Operator: Kaiser-Francis Oil Company
Name & P. O. Box 35528
Address Tulsa, OK 74135

County Stafford

Well Total Depth 4650 feet 8151.12

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 28 Month: September Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Buck Unruh

(company name) Kelso (phone) 316-938-2457

were: 5 1/2 set at 4600 PBTd 4325 Top Perf 3861 Bottom Perf 4254

1st plug pumped 100 sx cement on bottom and pushed plug to 3600.

2nd plug squeezed well with 3 sx hulls, 40 sx cement, 10 sx gel, 1 sack hulls and

released 8 5/8" rubber plug and pumped additional 85 sx cement

Maximum pressure 500# shut-in pressure 100#

Signed Steve Klumort
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:15 am Day: 28 Month: September Year: 19 83

ACTUAL PLUGGING REPORT 5 1/2 set at 4600' PBTd 4325 Perfs 3861 4254

1st plug pumped 100 sx cement on bottom and pushed plug to 3600'

2nd plug squeezed well with 3 sx hulls, 40 sx cement, 10 sx gel, 1 sack hulls and

released 8 5/8" rubber plug and pumped additional 85 sx cement

Maximum pressure 500# shut-in pressure 100#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun. Recovered 2175' of 5 1/2" casing.

Bud Metz gave the orders.

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 3-1-84
INV. NO. 0473

RECEIVED 2-29-84
STATE CORPORATION COMMISSION
FEB 29 1984
CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Klumort
(TECHNICIAN)