

To: 1120778 3-9  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

15-185-00474-0000 20 R  
API NUMBER 15- Drilled 10/24/58  
SE NW NE, SEC. 30, T. 25 S, R. 15 W/EX  
4290 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 8061  
Operator: Oil Producers, Inc. of Kansas  
Name & Address: P.O. Box 8647  
Wichita, KS 67208

Lease Name Lamb Well # 1  
County Stafford  
Well Total Depth 4400 143.00 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635  
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 9 Month: 3 Year: 1993

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

Perfs: 5 1/2" at 4398', PBTD 4335', Perfs at 4276-84'  
1st plug sand back to 4225' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper  
plug and pump 100' sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 11:30 a.m. Day: 9 Month: 3 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4225' and dumped 5 sx cement on top of sand  
through bailer,  
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 125  
sx cement.  
Pumping pressure 0-300 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied, Recovered 2314' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 3-24-93  
INV. NO. 32505

Signed Quinn Rankin  
(TECHNICIAN)