

To: 1 121106
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 047-21,252-0000
C SE , SEC. 1 , T 25 S, R 16 W/E
1320 feet from S section line
1320 feet from E section line

2-8

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061
Operator: Oil Producers, Inc. of Kansas
Name:
Address P.O. Box 8647
Wichita, KS 67208

Lease Name Miller Well # 1
County Edwards
Well Total Depth 4285 139.26 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 349

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10 a.m. Day: 8 Month: 2 Year: 1996

Plugging proposal received from Kent Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

work: 4 1/2" at 4281' w/100 sx cement, PBTD 4275', Perfs at 4224-36, 4249-55'
1st plug sand back to 4175' and dump 4 sx cement on top of sand through bailer,
2nd plug pump in surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Bill Johnson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45 a.m. Day: 8 Month: 2 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4175' and dumped 4 sx cement on
top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Pumping pressure 0-200 psi and shut in 50 psi.

RECEIVED
KANSAS CORPORATION COMMISSION
2-12-96
FEB 12 1996

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 4 1/2" casing.
(if additional description is necessary, use BACK of this report)

CONSERVATION DIVISION
WICHITA, KS

Observe this plugging.

INVOICED
DATE 2-28-96
INV. NO. 44896

Signed *David Rankin*
(TECHNICIAN)