

6-8-88

1 040114

API NUMBER 15-047-20,035-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C N/2 SE SE, SEC. 5, T 25 S, R 16 W/E
990 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5427

Lease Name Breitenbach "A" Well # 1

Operator: D.R. Lauck Oil Company, Inc.
Name & Address: 221 South Broadway, Suite 400
Wichita, KS 67202

County Edwards 150.90
Well Total Depth 4643 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 323

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 346, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 8 Month: 6 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4635' PBSD 4606' Perfs at 4250-60' Elevation 2081' GL

1st plug pump 2 sx hulls and 25 sx common cement.

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 8 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" with 200 lbs. of hulls and 25 sx common cement. Stopped plug at 4100', shut in pressure 500 psi.

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1988
7-21-88

Maximum pressure 500 psi and shut in 100 psi.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered approximately 2200' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

did not observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

INVOICED
DATE 6-30-88
INV. NO. 21128