

1 040505
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-4
3R
API NUMBER 15-047-20,252-0000

C NE, SEC. 17, T. 25, R. 16 W/E
3960 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Zuercher Well # 2

Operator: Oil Producers, Inc. of Kansas

County Edwards 144.78

Name & Address P.O. Box 8647

Well Total Depth 4455 feet

Wichita, KS 67208

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 319

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Oil Producers, Inc. of Kansas License Number 8061

Address P.O. Box 8647, Wichita, KS 67208

Company to plug at: Hour: 10:45 a.m. Day: 4 Month: 2 Year: 19 91

Plugging proposal received from Brad Siroky

(company name) Oil Producers, Inc. of Kansas (phone) 316-681-0231

were: 4 1/2" at 4454' w/150 sx cement, PBD 4424', Perfs at 4322-4400' (3 sets)

4 1/2" casing squeezed twice at 450' with a total of 375 sx cement, cement circulated.

1st plug fill 4 1/2" casing with cement,

2nd plug check backside.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 4 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 300 lbs. hulls and 210 sx cement. Maximum pressure 1200 psi and shut in 800 psi.

Pumped down 8 5/8" X 4 1/2" annulus. Pressured to 900#-held. Couldn't pump into it.

Remarks: Used 65/35 Pozmix 8% gel by B.J. Services. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
(Do not check this box) observe this plugging.

DATE 2-27-91

INV. NO. 30929

Signed Stephen J. Pifer
(TECHNICIAN)