

To: 1 052186
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

11-3

API NUMBER 15- 047-20,261-0000
C NE SE, SEC. 16, T 25 S, R 16 WXX
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5427
Operator: D.R. Lauck Oil Co., Inc.
Name & Address: 221 S. Broadway, Ste. 400
Wichita, KS 67202

Lease Name Meyer A Well # 2
County Edwards 14394
Well Total Depth 4429 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 375

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Quality Well Service License Number 31925
Address 249 Beth Dr., Sterling, KS 67579

Company to plug at: Hour: 2 p.m. Day: 3 Month: 11 Year: 1997

Plugging proposal received from Richard McIntyre
(company name) Quality Well Service (phone) 316-727-2410

logs: 5 1/2" at 4428' w/100 sx cement, PBTD 4399', Perfs at 4378-86, 4333-41, 4323-28'
Top of tubing fish at 3800', top of rod fish at 300'

11-3-97

1st plug sand back on top of tubing fish and dump 5 sx cement on top,
2nd plug run tubing to 850' and pump 8 sx gel, 50 sx cement, 200 lbs. hulls, 2 sx gel,
3rd plug pull tubing to 390' and pump 50 sx cement, 4th plug pull tubing to 200' and pump 35 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 4:30 p.m. Day: 3 Month: 11 Year: 1997

ACTUAL PLUGGING REPORT 1st plug drove wooden plug to 3000' and dumped 50' of sand, dumped 5 sx cement on top of sand. Ran tubing to 850',
2nd plug pumped 8 sx gel, 50 sx cement with 200 lbs. hulls displaced with 2 sx gel at 850',
3rd plug pulled tubing to 390' and pumped 50 sx cement. Waited 1 hour on cement.
4th plug pulled tubing to 200' and pumped 35 sx cement, circulating cement to surface.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 618' of 5 1/2" casing.

INVOICED

I (did / ~~XXXXXX~~) observe this plugging.
DATE 11-24-97
INV. NO. 49507

Signed Richard W. Lauck (TECHNICIAN)